



## Quotation Advert

Opening Date: 12/02/2025  
Closing Date: 21/02/2025  
Closing Time: 11:00

### INSTITUTION DETAILS

Institution Name: Rietvlei Hospital  
Province: KwaZulu-Natal  
Department of entity: Department of Health  
Division or section: Central Supply Chain Management  
Place where goods/  
service is required: RIETVLEI HOSPITAL  
Date Submitted: 12/02/2025

### ITEM CATEGORY AND DETAILS

Quotation number: RVH: 227/02/2024/2025  
Item Category: Services  
Item Description: Supply & Install 200 litres, high pressure geyser  
Quantity (if supplies): N/A

### COMPULSORY BRIEFING SESSION / SITE VISIT

Select Type: Compulsory Site Meeting  
Date: 17/02/2025  
Time: 10h: 00

Venue: Nursing Hall

QUOTES CAN BE COLLECTED FROM: ATTACHED ON ADVERT

QUOTES SHOULD BE DELIVERED TO: To Rietvlei Hospital Security gate

NB: PLEASE PRINT DOCUMENT ON WEBSITE, OFFICIAL STAMP WILL BE STAMPED ON SITE BRIEFING.

ENQUIRIES REGARDING ADVERT MAY BE DIRECTED TO:

Name: Lungile

Email: rietvlei.aq@gmail.com

Contact number: 060-3371475

Finance Manager Name: Mr P.S Biyase

Finance Manager Signature 

PROVINCE OF KWAZULU-NATAL

DEPARTMENT OF HEALTH

ZNQ-

**RIETVLEI DISTRICT HOSPITAL – SUPPLY AND INSTALLATION OF 200 LITRES HIGH PRESSURE GEYSER AT MALE AND FEMALE SURGICAL WARDS X2 (RIETVLEI HOSPITAL**

**1.1 SCOPE OF CONTRACT**

This Contract is for the execution of the project above.

**1.2 CONTRACT DRAWINGS**

No drawings

**1.3 CONDITIONS OF CONTRACT AND PRELIMINARIES**

**1.3.1 PERIOD OF CONTRACT**

One (01) week as the contract period for the completion of the work from date of site handover.

**1.3.2 CONTRACT GUARANTEE**

The successful Bidder will **NOT** be required to submit a contract guarantee

**1.3.3 GUARANTEE PERIOD**

The guarantee period for the completion of the structural work and all materials must be a minimum of **6 Calendar months** from the date of first delivery.

**1.3.4 SITE AND MORE PROCEDURE**

The work contained in this contract will be carried out on the site of the existing

**At RIETVLEI DISTRICT HOSPITAL.**

The Bidder is advised that the existing premises will be occupied throughout the period of the contract, and the minimum amount of disruption to services is of the outmost importance. Damage to the existing buildings- Bidders to note that any damages done or occurring to any of the building will be repaired at the expense of the contractor / Bidder . The repair must be to the satisfaction of the KwaZulu-natal Department of Health. Bidders are advised to visit the site prior to tendering and to Acquaint themselves with the nature of the work to be done and the access to the siting of the existing building etc., as no claim whatsoever will be allowed on the grounds of ignorance of the conditions under which the work will be executed.

### **1.3.5 SATISFACTORY INSTALLATION**

The whole of the installation shall be carried out in accordance with the South African Bureau of Standards Code of Practice for the application of National Building Regulations, the KZNPA Standard Preambles to all Trades, the KZNPA General Electrical Specification, ICASA, Telecommunications regulations, the South African Bureau of Standards Code of Practice for the Wiring of Premises SABS 0142 and the Occupational Health and Safety Act and Regulations 85/1993 as amended. Copies of the KZNPA Standard Preambles to all Trades and the Secretary for Health KwaZulu-Natal and can be obtained on the request.

### **1.3.6 CERTIFICATE OF COMPLIANCE**

On completion of the service, a copy of the "Certificate of Compliance for Electrical Installation" must be submitted to the office of the Secretary for Health: KwaZulu –Natal.

### **1.3.7 GENERAL**

The Bidder's / Contractors will be responsible for all masonry work associated with the electrical installation and making good of all work related to the electrical installation. The patching and painting must be to the satisfaction of the KwaZulu-Natal Department of Health.

---

## **TECHNICAL SPECIFICATIONS**

### **2. TECHNICAL SPECIFICATION**

#### **2.1 GENERAL**

This TECHNICAL SPECIFICATION shall be read in conjunction with all other sections of the SPECIFICATION and cognizance shall be taken of the clauses relevant to this particular installation, whether any specific clauses are referred to or not.

#### **2.2 STANDARD PREAMBLES**

This is available from the department on request.

### **2.3 HEALTH AND SAFETY SPECIFICATION**

Health and Safety Plan with Risk assessment schedule is to be compiled taking cognisance of the specific type of patient's that walk around the institution all day. All areas are to be protected at all times from patients falling in. All new and old Materials are to be securely stored during construction to eliminate any person from rolling them around or playing inside them.

**Grading: 1GB And above**

#### **CIDB COMPLIANCE**

- 2.4 Amendments: Functionality in different contracting strategies in line with regulations 4.3.3 of the CIDB regulations, where functionality is evaluated, at least by three Persons who are fully conversant with the Technical aspects of the scope of works shall undertake such evaluation.**

### **3. SCOPE OF WORK**

---

The work to be carried out under this contract includes the supply of all materials, and including all labour to carry out all electrical work and leaving in service condition to the satisfaction of the Secretary for Health: KwaZulu- Natal.

#### **3.1 The work comprises of**

- (a) Supply and installation of High pressure 200l Geyser. X2
- (b) Supply Geyser tray and connect 50mm PVC pipes from ceiling to outside.x2
- (c) Supply and connect power to both geysers.
- (d) Feed copper pipe to existing water lines from both geysers
- (e) Supply and installation of stop end feed from non-functioning calorifiers.
- (f) Supply Electrical compliance certificate after job completion.

## SCHEDULE OF RATES

### 4.1 ITEMS AND PRICING

The Department reserves the right to place an order for any quantities of items included in the schedules. The schedule of rates must also not be assumed to include and describe every detail of the supply requirement, but must be taken and read in conjunction with the other parts of the document. Thus the supplier shall not have claim for further payment in respect of any order which may be described or implied in the contract, although apparently no corresponding items are given in the schedule rates. The supplier shall be deemed to have satisfied himself before quoting as to correctness and sufficiency of his quote for contract and the rates and prices stated in the Schedule of Rates.

### 4.2 TAX AND DUTIES

Prices, quoted and paid, must include all customs, excise and import duties, and any other tariffs or taxes levied by the government or statutory body having jurisdiction on the goods provided under this contract, **including Value Added Tax (applicable to the current rate)**.

### 4.3 RATES

Except where provision is made in the Schedule of Rates, the rates and prices inserted shall be the full rates and prices for the service delivered described under the respective items and shall cover all labor, transport, overhead charges and profit, etc. as well as the general liabilities, obligations and risks arising out of the Condition of Contract, the overhead charges and profit being spread proportionately over the rates of the relative items in the Schedule of Rates.

---

Item no	Description	Unit	Qty	Rate	Total
	<b>SUPPLY AND INSTALL HIGH PRESSURE GEYSERS AND THE FOLLOWING ACCESSORIES:</b>				
1.	200L High pressure geyser 5 year guarantee SABS approved.	<del>02 No</del>	02		
2.	22mm copper pipe (SABS) 5 to 10 miters length and joints.				
3.					
4.	15mm copper pipe (SABS) 10 to 15 miters and joints.				
5.					
6.	Geyser trays and 50mm PVC pipe 6 to 15 meters length of PVC pipe.	<del>02 No</del>			
7.	Pressure control valves and vacuum breakers.	<del>02 No</del>			
8.	20 amps circuit breakers.	<del>02 No</del>			
9.	2,5 electrical cable supply 20 to 40 miters with 20 mm electrical conjute.	<del>02 No</del>			
10.	Geyser electrical isolator switch.	No	02		
11.	Electrical compliance.	No	02		
12.	32 to 38 mm compression fitting stop end.	No	02		
13.	Gate valve for geyser water isolator.	No	02		

--	--	--	--	--	--

The following documents must be returned with the quotation

- CIDB Registration certificate 1GB and above
- Valid Tax Clearance

COMPILED BY: SB Nkosi 

CHIEF ARTISAN AT RIETVLEI DISTRICT HOSPITAL

---