

ZNB 5035/2022-H – AMENDMENTS AND NOTES

1. BOTH INSTALLATIONS TO ENSURES **72 HOURS STANDBY AT 100% LOAD**
2. CIDB 3EP **OR** 3EB
3. LOCATION: ETHEKWINI – NEAR MCCORDS HOSPITAL
4. CONTRACT DURATION: 9 MONTHS
5. BOTH GENERATORS, INCLUDING CANOPY, BASE FRAME, BASE TANK AND BULK TANK TO BE CONSTRUCTED WITH 3CR12 MATERIAL
6. BASE TANK MINIMUM CAPACITY OF 1000L
7. NOTE: DEEP CYCLE LITHIUM IRON BATTERIES WITH MINIMUM WARRANTY OF 10 YEARS
8. IT WOULD BE BENEFICIAL (NOT COMPULSORY) TO PROVIDE RATES FOR A THIRD SERVICE DUE TO THE HIGH INCIDENCE OF LOAD SHEDDING. DO NOT INCLUDE IN THE PRICE MERELY HIGHLIGHT THE ESTIMATED COSTS SUCH THAT IT IS EASIER TO BUDGET FOR IF A VO IS REQUIRED.
9. TREE AND FOLIAGE REMOVAL IS THE COST OF THE CONTRACTOR AND TO BE INCLUDED IN CIVIL/BUILDING WORKS.
10. NOTE SOUND ATTENUATION <70DB
11. COMPLETE PART FOUR: SCHEDULE OF EQUIPMENT